

# NEWFIELD



Route #3 Box 3630  
Myton, Utah 84052  
(435) 646-4825, FAX: (435) 646-3031

April 2, 2009

State of Utah  
Division of Oil, Gas & Mining  
Attn: Diana Mason  
1594 West North Temple - Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Applications for Permit to Drill  
Lamb 16-19-4-1  
Tanner-Jorgenson 13-22-4-1  
Tanner-Jorgenson 15-22-4-1  
Wilcken 16-24-4-2

RECEIVED  
APR 06 2009  
DIV. OF OIL, GAS & MINING

Dear Diana:

Enclosed find APD's on the above referenced wells. They are all Fee/Fee Locations. I have included a copy of all Surface Use Agreements. If you have any questions, feel free to give either Dave Allred or myself a call.

Sincerely,

Mandie Crozier  
Regulatory Specialist

mc  
enclosures

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>Fee</b>	6. SURFACE: <b>Fee</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>NA</b>	
B. TYPE OF WELL: <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input checked="" type="checkbox"/> <b>MULTIPLE ZONE</b> <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: <b>NA</b>	
2. NAME OF OPERATOR: <b>Newfield Production Company</b>				9. WELL NAME and NUMBER: <b>Lamb 16-19-4-1</b>	
3. ADDRESS OF OPERATOR: <b>Route #3 Box 3630</b> CITY <b>Myton</b> STATE <b>UT</b> ZIP <b>84052</b>			PHONE NUMBER: <b>(435) 646-3721</b>		
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: <b>SE/SE 703' FSL 637' FEL</b>  AT PROPOSED PRODUCING ZONE: <b>582533x 40.115317</b> <b>4440796y -110.631286</b>				10. FIELD AND POOL, OR WILDCAT: <b>Monument Butte</b>	
				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SESE 19 4S 1W</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>Approximately 8.3 miles southeast of Myton, Utah</b>				12. COUNTY: <b>Duchesne</b>	
				13. STATE: <b>UTAH</b>	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>Approx. 637' f/lse line, NA' f/unit line</b>		16. NUMBER OF ACRES IN LEASE: <b>NA</b>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40 acres</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>NA</b>		19. PROPOSED DEPTH: <b>6,970</b>		20. BOND DESCRIPTION: <b>#B001834</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5228' GL</b>		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: <b>(7) days from SPUD to rig release</b>	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4	8 5/8	J-55	24.0	300	Class G w/2% CaCl	155 sx +/-	1.17    15.8
7 7/8	5 1/2	J-55	15.5	6,970	Lead(Prem Lite II)	275 sx +/-	3.26    11.0
					Tail (50/50 Poz)	450 sx +/-	1.24    14.3

**RECEIVED**  
**APR 06 2009**

25. ATTACHMENTS		<b>DIV. OF OIL, GAS &amp; MINING</b>	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:			
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN		
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER		

NAME (PLEASE PRINT) <u>Mandie Crozier</u>	TITLE <u>Regulatory Specialist</u>
SIGNATURE <u><i>Mandie Crozier</i></u>	DATE <u>4/2/09</u>

(This space for State use only)

API NUMBER ASSIGNED: 43-013-34257

APPROVAL:

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 04/06/2009

API NO. ASSIGNED: 43-013-34257

WELL NAME: LAMB 16-19-4-1

OPERATOR: NEWFIELD PRODUCTION ( N2695 )

PHONE NUMBER: 435-646-3721

CONTACT: MANDIE CROZIER

PROPOSED LOCATION:

SESE 19 040S 010W

SURFACE: 0703 FSL 0637 FEL

BOTTOM: 0703 FSL 0637 FEL

COUNTY: DUCHESNE

LATITUDE: 40.11532 LONGITUDE: -110.03129

UTM SURF EASTINGS: 582553 NORTHINGS: 4440796

FIELD NAME: MONUMENT BUTTE ( 105 )

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	D&D	6/17/09
Geology		
Surface		

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

SURFACE OWNER: 4 - Fee

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. 6001834 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
(No. 43-7478 )  
☒ RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )  
☒ Fee Surf Agreement (Y/N)  
☒ Intent to Commingle (Y/N)


LOCATION AND SITING:

       R649-2-3.  
Unit: \_\_\_\_\_  
☒ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
       R649-3-3. Exception  
       Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
       R649-3-11. Directional Drill

COMMENTS: Need Presto (04-30-09)

STIPULATIONS: 1- Spacing Strip  
2- STATEMENT OF BASIS  
3- Surface (sg) Cont Strip






**API Number: 4301334257**  
**Well Name: LAMB 16-19-4-1**  
**Township 04.0 S Range 01.0 W Section 19**  
**Meridian: UBM**  
**Operator: NEWFIELD PRODUCTION COMPANY**

Map Prepared:  
Map Produced by Diana Mason

Units	Wells Query Events
<b>STATUS</b>	<all other values>
ACTIVE	<b>GIS_STAT_TYPE</b>
EXPLORATORY	<Null>
GAS STORAGE	APD
NF PP OIL	DRL
NF SECONDARY	GI
PI OIL	GS
PP GAS	LA
PP GEOTHERML	NEW
PP OIL	OPS
SECONDARY	PA
TERMINATED	PGW
<b>Fields</b>	POW
<b>STATUS</b>	RET
ACTIVE	SGW
COMBINED	SOW
Sections	TA
	TW
	WD
	WI
	WS





# Application for Permit to Drill

## Statement of Basis

5/12/2009

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
1398	43-013-34257-00-00		OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD		
Well Name	LAMB 16-19-4-1		Unit		
Field	MONUMENT BUTTE		Type of Work		
Location	SESE 19 4S 1W U 703 FSL 637 FEL GPS Coord (UTM) 582553E 4440796N				

### Geologic Statement of Basis

Newfield proposes to set 300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 500'. A search of Division of Water Rights records shows 11 water wells within a 10,000 foot radius of the center of Section 19. All wells are privately owned. Depth is listed for only 2 wells and are shown as 24 and 70 feet in depth. Water use is listed as irrigation, stock watering, and domestic use. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Surface casing should be extended to cover the estimated base of the moderately saline ground water.

Brad Hill  
APD Evaluator

5/12/2009  
Date / Time

### Surface Statement of Basis

The proposed location is approximately 8.0 road miles south of Myton, UT in a sub-drainage of Pleasant Valley Wash which drains into the Pariette Draw drainage of Duchesne County. Both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 13 miles downstream from the location. Broad flats in Pleasant Valley frequently used for agriculture and surrounding lands with broken topography which are unsuitable for agriculture, characterize the area. The topography is intersected by drainages with gentle to moderate side slopes. Access is by State, County and existing or planned oil field roads. Five hundred and ten feet of new construction across Lamb's private land will be required to reach the location.

The proposed Lamb 16-19-4-1 oil well location is on non-cultivated lands in south Pleasant Valley. The pad will be on a gentle north sloping flat. An abandoned canal is to the south and a swale to the east. This swale has riparian type vegetation and will not be intersected. No springs, streams, seeps or ponds are known to exist in the immediate area however a shallow water table is anticipated. The selected site appears to be a good location for constructing a pad, drilling and operating a well.

The Rex Lamb estate owns both the surface and minerals of the location. Mr. Carl Lamb was contacted regarding the pre-site visit. He did not attend. A signed Land Use Agreement exists.

Floyd Bartlett  
Onsite Evaluator

4/30/2009  
Date / Time

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** NEWFIELD PRODUCTION COMPANY  
**Well Name** LAMB 16-19-4-1  
**API Number** 43-013-34257-0 **APD No** 1398 **Field/Unit** MONUMENT BUTTE  
**Location:** 1/4, 1/4 SESE - - - - - **Sec** 19 **Tw** 4S **Rng** 1W 703 FSL 637 FEL  
**GPS Coord (UTM)** 582544 4440799 **Surface Owner**

### **Participants**

Floyd Bartlett (DOGM), Tim Eaton (Newfield Production Co.) Cory Miller (Tri State Land Surveying).

### **Regional/Local Setting & Topography**

The proposed location is approximately 8.0 road miles south of Myton, UT in a sub-drainage of Pleasant Valley Wash which drains into the Pariette Draw drainage of Duchesne County. Both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 13 miles downstream from the location. Broad flats in Pleasant Valley frequently used for agriculture and surrounding lands with broken topography which are unsuitable for agriculture, characterize the area. The topography is intersected by drainages with gentle to moderate side slopes. Access is by State, County and existing or planned oil field roads. Five hundred and ten feet of new construction across Lamb's private land will be required to reach the location.

The proposed Lamb 16-19-4-1 oil well location is on non-cultivated lands in south Pleasant Valley. The pad will be on a gentle north sloping flat. An abandoned canal is to the south and a swale to the east. This swale has riparian type vegetation and will not be intersected. No springs, streams, seeps or ponds are known to exist in the immediate area however a shallow water table is anticipated. The selected site appears to be a good location for constructing a pad, drilling and operating a well.

The Rex Lamb estate owns both the surface and minerals of the location. Mr. Carl Lamb was contacted regarding the pre-site visit. He did not attend.

### **Surface Use Plan**

#### **Current Surface Use**

Grazing  
Wildlife Habitat

#### **New Road**

<b>Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0.1	<b>Width</b> 199 <b>Length</b> 290	Onsite	UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

**Affected Floodplains and/or Wetland** N

#### **Flora / Fauna**

Deseret shrub type consisting of cheatgrass, halogeton, greasewood, shadscale and annuals exists.

Cattle, deer, prairie dogs, small mammals and birds.

**Soil Type and Characteristics**

Moderately deep sandy loam.

**Erosion Issues** N**Sedimentation Issues** N**Site Stability Issues** N**Drainage Diversion Required** N**Berm Required?** N**Erosion Sedimentation Control Required?** N**Paleo Survey Run?** N**Paleo Potential Observed?** N**Cultural Survey Run?** N**Cultural Resources?****Reserve Pit****Site-Specific Factors****Site Ranking****Distance to Groundwater (feet)** 25 to 75

15

**Distance to Surface Water (feet)** >1000

0

**Dist. Nearest Municipal Well (ft)** >5280

0

**Distance to Other Wells (feet)** >1320

0

**Native Soil Type** Mod permeability

10

**Fluid Type** Fresh Water

5

**Drill Cuttings** Normal Rock

0

**Annual Precipitation (inches)** <10

0

**Affected Populations** <10

0

**Presence Nearby Utility Conduits** Not Present

0

**Final Score**

30

1

**Sensitivity Level****Characteristics / Requirements**

The reserve pit is 40' x 80' x 8' deep located in an area of cut on the northeast side of the location. A pit liner is required. Newfield commonly uses a 16-mil liner.

**Closed Loop Mud Required?** N**Liner Required?** Y**Liner Thickness** 16**Pit Underlayment Required?** Y**Other Observations / Comments**


Floyd Bartlett

4/30/2009

**Evaluator****Date / Time**

43013342570000 Lamb 16-19-4-1

Casing Schematic





Well name:	<b>43013342570000 Lamb 16-19-4-1</b>	
Operator:	<b>Newfield Production Company</b>	
String type:	<b>Surface</b>	Project ID: <b>43-013-34257-0000</b>
Location:	<b>Duchesne County</b>	

**Design parameters:**

**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 72 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 185 ft

Cement top: 221 ft

**Burst**

Max anticipated surface pressure: 440 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 500 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 437 ft

**Non-directional string.**

**Re subsequent strings:**

Next setting depth: 6,970 ft  
Next mud weight: 8.400 ppg  
Next setting BHP: 3,041 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 500 ft  
Injection pressure: 500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	500	8.625	24.00	J-55	ST&C	500	500	7.972	178.8

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	218	1370	6.279	500	2950	5.90	12	244	20.33 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 810-538-5357

Date: June 4, 2009  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 500 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:

**43013342570000 Lamb 16-19-4-1**Operator: **Newfield Production Company**String type: **Production**

Project ID:

**43-013-34257-0000**Location: **Duchesne County****Design parameters:****Collapse**Mud weight: 8.400 ppg  
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 163 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 1,361 ft

**Burst**Max anticipated surface  
pressure: 1,508 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 3,041 psi

No backup mud specified.

**Tension:**8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)**Non-directional string.**Tension is based on buoyed weight.  
Neutral point: 6,084 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6970	5.5	15.50	J-55	LT&C	6970	6970	4.825	931.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3041	4040	1.328	3041	4810	1.58	94	217	2.30 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 810-538-5357

Date: June 4, 2009  
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 6970 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*



**BOPE REVIEW**
**Newfield Lamb 16-19-4-1**
**API 43-013-34257-0000**
**INPUT**

Well Name

Newfield Lamb 16-19-4-1 API 43-013-34257-0000			
String 1	String 2		
8 5/8	5 1/2		
500	6970		
0	500		
8.4	8.4	✓	
0	2000		
2950	4810		
3018	8.3 ppg	✓	

Casing Size (")

Setting Depth (TVD)

Previous Shoe Setting Depth (TVD)

Max Mud Weight (ppg)

BOPE Proposed (psi)

Casing Internal Yield (psi)

Operators Max Anticipated Pressure (psi)

**Calculations**
**String 1 8 5/8 "**
**Max BHP [psi]**
 $.052 \times \text{Setting Depth} \times \text{MW} = 218$ 
**BOPE Adequate For Drilling And Setting Casing at Depth?**
**MASP (Gas) [psi]**
 $\text{Max BHP} - (0.12 \times \text{Setting Depth}) = 158$ 

NO

 Air drill *OK*
**MASP (Gas/Mud) [psi]**
 $\text{Max BHP} - (0.22 \times \text{Setting Depth}) = 108$ 

NO

**\*Can Full Expected Pressure Be Held At Previous Shoe?**
**Pressure At Previous Shoe**  $\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) = 108$ 

NO

*Reasonable Depth*
**Required Casing/BOPE Test Pressure**

500

psi

**\*Max Pressure Allowed @ Previous Casing Shoe =**

0

psi

\*Assumes 1psi/ft frac gradient

**Calculations**
**String 2 5 1/2 "**
**Max BHP [psi]**
 $.052 \times \text{Setting Depth} \times \text{MW} = 3044$ 
**BOPE Adequate For Drilling And Setting Casing at Depth?**
**MASP (Gas) [psi]**
 $\text{Max BHP} - (0.12 \times \text{Setting Depth}) = 2208$ 

NO

**MASP (Gas/Mud) [psi]**
 $\text{Max BHP} - (0.22 \times \text{Setting Depth}) = 1511$ 

YES

*OK*
**\*Can Full Expected Pressure Be Held At Previous Shoe?**
**Pressure At Previous Shoe**  $\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) = 1621$ 

NO

*Reasonable for a re-y*
**Required Casing/BOPE Test Pressure**

2000

psi

**\*Max Pressure Allowed @ Previous Casing Shoe =**

500

psi

\*Assumes 1psi/ft frac gradient

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>Fee</b>		6. SURFACE <b>Fee</b>	
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>NA</b>			
8. TYPE OF WELL: <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input checked="" type="checkbox"/> <b>MULTIPLE ZONE</b> <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: <b>NA</b>			
2. NAME OF OPERATOR: <b>Newfield Production Company</b>				9. WELL NAME and NUMBER: <b>Lamb 16-19-4-1</b>			
3. ADDRESS OF OPERATOR: <b>Route #3 Box 3630</b> CITY <b>Myton</b> STATE <b>UT</b> ZIP <b>84052</b>				PHONE NUMBER: <b>(435) 646-3721</b>			
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: <b>SE/SE</b> <b>703' FSL 637' FEL</b>  AT PROPOSED PRODUCING ZONE:				10. FIELD AND POOL, OR WILDCAT: <b>Monument Butte</b>			
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SESE 19 4S 1W</b>							
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>Approximately 8.3 miles southeast of Myton, Utah</b>				12. COUNTY: <b>Duchesne</b>		13. STATE: <b>UTAH</b>	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>Approx. 637' f/lse line, NA' f/unit line</b>		16. NUMBER OF ACRES IN LEASE: <b>NA</b>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40 acres</b>			
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>NA</b>		19. PROPOSED DEPTH: <b>6,970</b>		20. BOND DESCRIPTION: <b>#B001834</b>			
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5228' GL</b>		22. APPROXIMATE DATE WORK WILL START: <b>3rd Qtr. 2009</b>		23. ESTIMATED DURATION: <b>(7) days from SPUD to rig release</b>			

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4	8 5/8	J-55	24.0	<b>500</b>	Class G w/2% CaCl	175 sx +/-	1.17    15.8
7 7/8	5 1/2	J-55	15.5	6,970	Lead(Prem Lite II)	275 sx +/-	3.26    11.0
					Tail (50/50 Poz)	450 sx +/-	1.24    14.3

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <u>Mandie Crozier</u>	TITLE <u>Regulatory Specialist</u>
SIGNATURE <u><i>Mandie Crozier</i></u>	DATE <u>5/15/09</u>

(This space for State use only)

API NUMBER ASSIGNED: 43-013-34257

**Approved by the  
Utah Division of  
Oil, Gas and Mining**  
APPROVAL:

**RECEIVED**

**MAY 15 2009**

DIV. OF OIL, GAS & MINING



Date: 5-15-09  
(See Instructions on Reverse Side)  
By: *[Signature]*




**T4S, R1W, U.S.B.&M.**

**NEWFIELD PRODUCTION COMPANY**

WELL LOCATION, WELL 16-19-4-1W,  
LOCATED AS SHOWN IN THE SE 1/4 SE  
1/4 OF SECTION 19, T4S, R1W,  
U.S.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. No.189377



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV;  
U.S.G.S. 7-1/2 min QUAD (MYTON SE)

**WELL 16-19-4-1W**  
(Surface Location) NAD 83  
LATITUDE = 40° 06' 55.07"  
LONGITUDE = 110° 01' 55.55"

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
(435) 781-2501

DATE SURVEYED: 06/23/08	SURVEYED BY: T.H.
DATE DRAWN: 07/02/08	DRAWN BY: R.A.B.
REVISED:	SCALE: 1" = 1000'

NEWFIELD PRODUCTION COMPANY  
LAMB 16-19-4-1  
SE/SE SECTION 19, T4S, R1W  
DUSCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0 – 1,920'
Green River	1,920'
Wasatch	6,970'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1,920' – 6,970'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO <sub>3</sub> ) (mg/l)
Dissolved Bicarbonate (NaHCO <sub>3</sub> ) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO <sub>4</sub> ) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM:**

Surface Casing: 8-5/8" J-55 24# w/ST&C collars; set at 500' (New)  
Production Casing: 5-1/2" J-55, 15.5# w/LT&C collars; set at TD (New or used, inspected)

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

RECEIVED

JUN 08 2009

DIV. OF OIL, GAS & MINING



An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to  $\pm 350$  feet will be drilled with an air/mist system. From about 350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite.

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 500' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the second quarter of 2009, and take approximately seven (7) days from spud to rig release.

NEWFIELD PRODUCTION COMPANY  
LAMB 16-19-4-1  
SE/SE SECTION 19, T4S, R1W  
DUSCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. **EXISTING ROADS**

See attached **Topographic Map "A"**

To reach Newfield Production Company well location site Lamb 16-19-4-1 located in the SE¼ SE¼ Section 19, T4S, R1W, S.L.B. & M., Duchesne County, Utah:

Proceed in a southerly direction out of Myton, approximately 3.0 miles to it's junction with an existing road to the east; proceed in a southeasterly direction approximately 3.2 miles to it's junction with an existing road to the east; proceed in an easterly direction approximately 1.3 miles to it's junction with an existing road to the southwest; proceed in an southwesterly direction approximately 0.5 miles to it's junction with the beginning of the proposed access road; proceed along the proposed access road approximately 1820' to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. **PLANNED ACCESS ROAD**

Approximately 1820' of access road is proposed. See attached **Topographic Map "B"**.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to **EXHIBIT B**.

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District  
Water Right: 43-7478

Neil Moon Pond  
Water Right: 43-11787

Maurice Harvey Pond  
Water Right: 47-1358

Newfield Collector Well  
Water Right: 41-3530 (A30414DV, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous



will be placed in this pit. A 16 mil liner with felt will be required. Newfield requests approval that a flare pit be constructed and utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

**Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** Rex and LaRue Lamb Trust  
See attached Easement ROW and Surface Use Agreement.

12. **OTHER ADDITIONAL INFORMATION:**

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological and Paleontological Report Waiver is attached. See Exhibit "D".

**Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

**Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the Lamb 16-19-4-1, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Lamb 16-19-4-1 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

**13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Dave Allred  
Address: Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

## Certification

Please be advised that Newfield Production Company is considered to be the operator of well #16-19-4-1, SE/SE Section 19, T4S, R1W, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

Date 4/1/09

Mandie Crozier  
Regulatory Specialist  
Newfield Production Company



A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative


Name: Dave Allred  
Address: Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #16-19-4-1, SE/SE Section 19, T4S, R1W, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

4/1/09  
Date

  
Mandie Crozier  
Regulatory Specialist  
Newfield Production Company

MEMORANDUM  
of  
EASEMENT, RIGHT-OF-WAY  
and  
SURFACE USE AGREEMENT

This Easement, Right-of-Way and Surface Use Agreement ("Agreement") is entered into this 23rd day of June, 2008 by and between **Rex and LaRue Lamb, Karl Lamb, trustee whose address is PO Box 374, Myton Utah 84052**, ("Surface Owner," whether one or more) and Newfield Production Company, a Texas corporation ("NEWFIELD"), with offices at 1001 17<sup>th</sup> Street, Suite 2000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Duchesne County, Utah described as follows:

Township 4 South, Range 1 East  
Section 34, NWNW

Uintah County, Utah  
being 40 acres, more or less

Township 4 South, Range 1 West  
Section 19, SESE

Duchesne County, Utah  
being 40 acres, more or less

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. Compensation for Well; Release of All Claims

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right-of Way and Surface Use by and between Surface Owner and NEWFIELD, dated June 23rd, as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. Grant of Right of Way and Easement

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.

This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned. This agreement replaces and supersedes any and all prior agreements covering the lands described herein.

These Parties hereto have executed this document effective as of the day first above written.

SURFACE OWNER

NEWFIELD PRODUCTION COMPANY

By: \_\_\_\_\_

Name: Karl Lamb  
Title: Trustee

By: \_\_\_\_\_

Gary D. Packer, President

STATE OF UTAH )

COUNTY OF DUCHESNE )


)ss

This instrument was acknowledged before me this 25 day of June, 2008 by

Witness my hand and official seal.

David Allred  
Notary Public

My commission expires July 5 2011



STATE OF COLORADO )

COUNTY OF DENVER )

)ss

This instrument was acknowledged before me this \_\_\_\_\_, 2008 by  
**Gary D. Packer, as President of Newfield Production Company, a Texas corporation, on behalf of the**  
corporation.

Witness my hand and official seal.


\_\_\_\_\_  
Notary Public

My commission expires \_\_\_\_\_

# NEWFIELD PRODUCTION COMPANY

WELL 16-19-4-1W

Section 19, T4S, R1W, U.S.B.&M.



## REFERENCE POINTS

170' NORTHWESTERLY 5226.1'  
 220' NORTHWESTERLY 5226.1'  
 210' SOUTHWESTERLY 5234.8'  
 260' SOUTHWESTERLY 5238.6'





SURVEYED BY: T.H.	DATE SURVEYED: 06/23/08
DRAWN BY: R.A.B.	DATE DRAWN: 07/03/08
SCALE: 1" = 50'	REVISED:

**Tri State**  
 Land Surveying, Inc.  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
 (435) 781-2501



# NEWFIELD PRODUCTION COMPANY

## CROSS SECTIONS WELL 16-19-4-1W



NOTE:  
UNLESS OTHERWISE  
NOTED ALL CUT/FILL  
SLOPES ARE AT 1.5:1

### ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)



ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	2,210	1,570	Topsoil is not included in Pad Cut	640
PIT	640	0		640
TOTALS	2,850	1,570	970	1,280

SURVEYED BY: T.H.	DATE SURVEYED: 06/23/08
DRAWN BY: R.A.B.	DATE DRAWN: 07/03/08
SCALE: 1" = 50'	REVISED:

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

# NEWFIELD PRODUCTION COMPANY

## TYPICAL RIG LAYOUT WELL 16-19-4-1W





SURVEYED BY: T.H.	DATE SURVEYED: 06/23/08
DRAWN BY: R.A.B.	DATE DRAWN: 07/03/08
SCALE: 1" = 50'	REVISED:

**Tri State**  
Land Surveying, Inc.  
(435) 781-2501  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078









**NEWFIELD**  
Exploration Company

**Well 16-19-4-1W**  
**SEC. 19, T4S, R1W, U.S.B.&M.**





**Tri-State**  
Land Surveying Inc.  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'  
DRAWN BY: JAS  
DATE: 08-22-2008

**Legend**

Existing Road

Proposed Access


TOPOGRAPHIC MAP

"B"

















**NEWFIELD**  
Exploration Company

**Well 16-19-4-1W**  
**SEC. 19, T4S, R1W, U.S.B.&M.**



N



**Tri-State**  
Land Surveying Inc.  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: JAS

DATE: 08-22-2008

**Legend**

● Location

One-Mile Radius

**Exhibit "B"**

## 2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C



**EXHIBIT D**

Township 4 South, Range 1 West  
Section 19 SESE

Duchesne County, Utah

**ARCHAEOLOGICAL & PALEOTOLOGICAL REPORT WAIVER**

For the above referenced location; **Rex and LaRue Lamb Trust, Karl Lamb, trustee whose address is PO Box 374, Myton Utah 84052**, the Private Surface Owner. (Having a Surface Owner Agreement with Newfield Production Company)

Karl Lamb, representing this entity does agree to waive the request from the State of Utah and Bureau of Land Management for an Archaeological/Cultural and Paleotological Resource Survey for any wells covered by the Surface Use Agreement dated 6/23/2008 between the above said private land owner and Newfield Production. This waiver hereby releases Newfield Production Company from this request.

Karl Lamb 1-22-09  
Karl Lamb, Trustee Date  
Rex and LaRue Lamb Trust

Brad Mechem 1-22-09  
Brad Mechem Date  
Newfield Production Company



JON M HUNTSMAN, JR.  
Governor

GARY R HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R BAZA  
Division Director

June 18, 2009

Newfield Production Company  
Rt. #3, Box 3630  
Myton, UT 84052

Re: Lamb 16-19-4-1 Well, 703' FSL, 637' FEL, SE SE, Sec. 19, T. 4 South, R. 1 West,  
Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-34257.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Duchesne County Assessor



**Operator:** Newfield Production Company  
**Well Name & Number** Lamb 16-19-4-1  
**API Number:** 43-013-34257  
**Lease:** Fee

**Location:** SE SE **Sec.** 19 **T.** 4 South **R.** 1 West

### **Conditions of Approval**

#### **1. General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **2. Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

#### **3. Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

#### **4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)**

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
6. Surface casing shall be cemented to the surface.

Spud  
BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross Rig #  
29 Submitted By Don Bastian Phone  
Number 435-823-6012  
Well Name/Number Lamb 16-19-4-1  
Qtr/Qtr SE/SE Section 19 Township 4 S Range 1 W   
Lease Serial Number FEE  
API Number 43-013-34257

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 8/4/09 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 8/4/09 5:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELL

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL:

OIL WELL ☒ GAS WELL ☐ OTHER

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR:

Route 3 Box 3630 CITY Myton STATE UT ZIP 84052

PHONE NUMBER

435.646.3721

4. LOCATION OF WELL:

FOOTAGES AT SURFACE:

5. LEASE DESIGNATION AND SERIAL NUMBER:  
FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

LAMB 16-19-4-1

9. API NUMBER:

4301334257

10. FIELD AND POOL, OR WILDCAT:

MONUMENT BUTTE

COUNTY: DUCHESNE

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SESE, 19, T4S, R1W

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 08/07/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Spud Notice
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 8/4/09 MIRU Ross # 29. Spud well @ 8:00am on 8/5/09. Drill 540' of 12 1/4" hole with air mist. TIH W/ 12 Jt's 8 5/8" J-55 24 # csgn. Set @ 538.99' On 8/6/09 cement with 286 sks of class "G" w/ 2% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 6 bbls cement to pit. WOC.

NAME (PLEASE PRINT) Don Bastian

TITLE Drilling Foreman

SIGNATURE

DATE 08/07/2009

(This space for State use only)

RECEIVED

AUG 12 2009

DIV. OF OIL, GAS & MINING

<b>8 5/8"</b>	<b>CASING SET AT</b>	<b>538.99</b>
---------------	----------------------	---------------

OPERATOR Newfield Exploration Company  
WELL LAMB 16-19-4-1  
FIELD/PROSPECT Monument Butte  
CONTRACTOR & RIG # Ross Rig # 29

[illegible]

[illegible]

COMPANY REPRESENTATIVE

## Reed Durfey

DATE 8/7/2009

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING  
ENTITY ACTION FORM -FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY  
ADDRESS: RT. 3 BOX 3630  
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	17346	4301350018	HANCOCK 3-20-4-1	NENW	20	4S	1W	DUCHESNE	8/7/2009	8/13/09
WELL 1 COMMENTS: GRV											
A	99999	17347	4301334257	LAMB 16-19-4-1	SESE	19	4S	1W	DUCHESNE	8/5/2009	8/13/09
GRV											
A	99999		4304740503	UTE TRIBAL 4-30-4-1E	NENW	30	4S	1E	UINTAH	7/16/2009	
Duplicate (submitted in July)											
A	99999	17348	4301333145	FEDERAL 9-21-9-16	NESE	21	9S	16E	DUCHESNE	7/31/2009	8/13/09
GRV											
B	99999	12276	4301334068	WELLS DRAW FEDERAL R-33-8-16	NWSE	33	8S	16E	DUCHESNE	7/29/2009	8/13/09
WELL 5 COMMENTS: GRV BHL = SWSE											
B	99999	12276	4301334067	WELLS DRAW FEDERAL S-33-8-16	NWSE	33	8S	16E	DUCHESNE	8/1/2009	8/13/09
WELL 5 COMMENTS: GRV BHL = SESE											

ACTION CODES (See instructions on back of form.)


- A - 1 new entity for new well (single well only)
- B - well to existing entity (group or unit well)
- C - from one existing entity to another existing entity
- D - well from one existing entity to a new entity
- E - ther (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED

AUG 12 2009

DIV. OF OIL, GAS & MINING

Signature:   
Production Clerk: Jentri Park  
Date: 08/12/09

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL: FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: LAMB 16-19-4-1
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SESE, 19, T4S, R1W		9. API NUMBER: 4301334257
		10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of Work Completion: 08/13/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 8/8/09MIRU NDSI Rig #3. Set all equipment. Pressure test Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 478'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 6715'. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 150 jt's of 5.5 J-55, 15.5# csgn. Set @ 6685.44' / KB. Cement with 300 sks cement mixed @ 11.0 ppg & 3.43 yld. The 425 sks cement mixed @ 14.4 ppg & 1.24 yld. circ 18 bbl cmt to surface. Nipple down Bop's. Set slips @ 109,000 #'s tension. Release rig 11:30 PM on 8/13/09.

NAME (PLEASE PRINT) Johnny Davis	TITLE Drilling Foreman
SIGNATURE 	DATE 08/14/2009

(This space for State use only)

**RECEIVED**

**AUG 25 2009**

**DIV. OF OIL, GAS & MINING**



# NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

5 1/2" CASING SET AT 6685.44

LAST CASING 8 5/8" SET AT 539  
 DATUM 12  
 DATUM TO CUT OFF CASING \_\_\_\_\_  
 DATUM TO BRADENHEAD FLANGE \_\_\_\_\_  
 TD DRILLER 6715 LOGC 6719  
 HOLE SIZE 7 7/8"

OPERATOR Newfield Exploration Company  
 WELL LAMB 16-19-4-1  
 FIELD/PROSPECT Monument Butte  
 CONTRACTOR & RIG # NDSI Rig #3

LOG OF CASING STRING:							
PIECES	OD	ITEM - MAKE - DESCRIPTION		WT / FT	GRD	THREAD	COND T
1	5 1/2"	Landing joint		15.5	J-55	LTC	A
149	5 1/2"	LT&C Csg.		15.5	J-55	LTC	A
1	5 1/2"	Float collar					A
1	5 1/2"	Shoe jt Csg.		15.5	J-55	LTC	A
1	5 1/2"	Guide shoe					A
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			
TOTAL LENGTH OF STRING		6687.44		LESS CUT OFF PIECE			
LESS NON CSG. ITEMS		16.61		PLUS DATUM TO T/CUT OFF CSG			
PLUS FULL JTS. LEFT OUT		315.72	7	CASING SET DEPTH			
TOTAL		6986.55	7				
TOTAL CSG. DEL. (W/O THRDS)		6986.55	157	} COMPARE			
TIMING							
BEGIN RUN CSG.	Spud	3:00 PM	8/13/2009	GOOD CIRC THRU JOB <u>Yes</u>			
CSG. IN HOLE		5:30 PM	8/13/2009	Bbls CMT CIRC TO SURFACE _____			
BEGIN CIRC		5:30 PM	8/13/2009	RECIPROCATED PIPI <u>Yes</u>			
BEGIN PUMP CMT		5:32 PM	8/13/2009				
BEGIN DSPL. CMT		6:18 AM	8/13/2009	BUMPED PLUG TO <u>2280</u>			
PLUG DOWN		6:42 AM	8/13/2009				

[illegible]

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL: FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: LAMB 16-19-4-1
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SESE, 19, T4S, R1W		9. API NUMBER: 4301334257
		10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 09/24/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was completed on 09-09-09, attached is a daily completion status report.

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	TITLE Production Tech
SIGNATURE 	DATE 09/24/2009

(This space for State use only)

RECEIVED  
SEP 28 2009  
DIV. OF OIL, GAS & MINING

**Daily Activity Report****Format For Sundry****LAMB 16-19-4-1****7/1/2009 To 11/30/2009****8/27/2009 Day: 1****Completion**

Rigless on 8/27/2009 - Ran CBL & perforated 1st stage. - Install 5M frac head & NU Weatherford Cameron single blind BOP. RU HO trk & pressure test casing, wellhead, casing valves & blind rams to 4500 psi. RU Perforators LLC WLT & mast. Run CBL under pressure f/ WLTD of 6588' to sfc. Found cmt top @ 38'. Perforate stage #1, CP3 sds @ 6342-44', CP2 sds @ 6320- 22', 6315- 17', CP1 sds @ 6272- 76' W/ 3 1/8" slick gun (19 gm charge, .49" EH, 21.92" pen, 120° phasing & 3 JSPF) for a total of 30 holes. RD WLT. SIFN W/ est 157 BWTR.

**Daily Cost:** \$0**Cumulative Cost:** \$12,958**9/2/2009 Day: 2****Completion**

WWS #3 on 9/2/2009 - Frac & perforate 3 stages. Flowback well. MIRU WWS #3. - Stage #1, CP 3,2 & 1 sands. RU BJ Services. 100 psi on well. Broke down @ 3489 psi @ 3 BPM. ISIP 2007 psi. FG .75. 1 min 1885 psi, 5 min 1600 psi, 10 min 1457 psi, 15 min 1356 psi, 30 min 1193 psi, 45 min 1092 psi, 1 hr 1033 psi. Frac CP3,2 & 1 sds w/20,737#'s of 20/40 sand in 359 bbls of Lightning 17 fluid. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of psi @ ave rate of BPM. Pumped 504 gals of 15% HCL in flush for Stage #2. ISDP 2011 psi. Leave pressure on well. 516 BWTR - Stage #2, D2 & 1 sands. RU Perforators LLC WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 2,2,2,2 & 2' perf guns. Set plug @ 5550'. Perforate D2 sds @ 5458-60, 5453-55', D1 sds @ 5397-99' 5389-91' & 5378-80' w/ 3 1/8" port plug guns ( 11 gram, .36" HE, 120°, 16.82" pen,) w/ 3 spf for total of 30 shots. RU BJ Services. 960 psi on well. Broke down @ 1379 psi @ 4.6 BPM. No ISIP, 1 min or 4 min due to low psi. Frac D2 & 1 sds w/ 85,716#'s of 20/40 sand in 677 bbls of Lightning 17 fluid. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2295 psi @ ave rate of 41.3 BPM. Pumped 504 gals of 15% HCL in flush for Stage #3. ISDP 2003 psi. Leave pressure on well. 1193 BWTR - Stage #3, GB4 & GB6 sands. RU Perforators LLC WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 5,4 & 2' perf guns. Set plug @ 5010'. Perforate GB6 sds @ 4941-46', GB4 sds @ 4908-12', 4900-4902' w/ 3 1/8" port plug guns (11 gram, .36" HE, 120°, 16.82" pen,) w/ 3 spf for total of 33 shots. RU BJ Services. 1310 psi on well. Broke down @ 4247 psi @ 0 BPM. No ISIP, 1 min or 4 min due to low psi. Frac GB4 & GB6 sds w/ 101,374#'s of 20/40 sand in 761 bbls of Lightning 17 fluid. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2667 psi @ ave rate of 41.3 BPM. ISDP 2411 psi. Begin flowback on 20/64 choke @ 3 BPM. Flowed for 4 1/2 hrs & died. Rec 763 BTF. MIRU WWS rig #3. ND Cameron BOP & 5M WH. NU 3M WH & Schaffer BOP. SIWFN w/ 1191 BWTR

**Daily Cost:** \$0**Cumulative Cost:** \$111,819**9/4/2009 Day: 3****Completion**

WWS #3 on 9/4/2009 - DU CBPs. Swab for cleanup. 961 BWTR. - Csg. @ 150 psi. Bleed off well. RIH w/ 4 3/4" chomp bit, bit sub & new 2 7/8" tbg. from pipe racks (tallying & drifting). Well began flowing. Stab tbg. disc. Cont. RIH w/ tbg. Tag CBP @ 5010'. RU powerswivel & pump. DU CBP in 13 min. Cont. RIH w/ tbg. Tag CBP @ 5550'. DU CBP in 20 min. Cont. RIH w/ tbg. Tag fill @ 6546'. C/O to PBTD @ 6641'. Circulate well clean. RD powerswivel. Pull up

to 6578'. RIH w/ swab. SFL @ surface. Made 6 runs. Recovered 75 bbls water. Trace of oil. No show of sand. FFL @ 600'. SWIFN. 961 BWTR.

**Daily Cost:** \$0

**Cumulative Cost:** \$121,204

---

**9/8/2009 Day: 4****Completion**

WWS #3 on 9/8/2009 - Swab for cleanup. Round trip tbg. ND BOP. Start in hole w/ rods. - Tbg. @ 150 psi, csg. @ 50 psi. Bleed off well. Attempt to RIH w/ swab. Could not get in hole. RU pump to csg. Circulate well w/ 20 bbls water. RIH w/ swab. SFL @ surface. Made 7 runs. Recovered 155 bbls. Ending oil cut at approx. 15%. No show of sand. EFL @ 500'. RD swab. RIH w/ tbg. Tag PBTB @ 6641' (no new sand). Circulate well clean. POOH w/ tbg. LD BHA. RIH w/ 2 7/8" notched collar, 2 jts 2 7/8" tbg., PSN, 2 jts 2 7/8" tbg., 5 1/2" TAC & 197 jts 2 7/8" tbg. ND BOP. Set TAC @ 6284' w/ 19,000# tension. NU wellhead. X-over for rods. Flush tbg. w/ 60 bbls water. RIH w/ Central Hydraulic rod pump, 6- 1 1/2" weight bars, 20- 3/4" guided rods, 30- 3/4" plain rods. SWIFN w/ polished rod. 861 BWTR.

**Daily Cost:** \$0

**Cumulative Cost:** \$134,926

---

**9/9/2009 Day: 5****Completion**

WWS #3 on 9/9/2009 - PU rods. Put well on production @ 12:00 p.m. 122" stroke, 5 spm. Final Report. 861 BWTR. - Cont. RIH w/ rods. Seat pump. RU pumping unit. Hang off rods. Stroke test to 800 psi. Good pump action. RD. Put well on production @ 12:00 p.m. 122 stroke length, 5 spm. Final Report. 861 BWTR. **Finalized**

**Daily Cost:** \$0

**Cumulative Cost:** \$155,088

---

**Pertinent Files: Go to File List**



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0137  
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other  
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,  
Other: \_\_\_\_\_

2. Name of Operator  
NEWFIELD EXPLORATION COMPANY

3. Address  
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)  
(435)646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)\*

At surface 703' FSL & 637' FEL (SE/SE) SEC. 19, T4S, R1W

At top prod. interval reported below

At total depth 6715'

14. Date Spudded  
08/05/2009

15. Date T.D. Reached  
08/13/2009

16. Date Completed 09/09/2009  
☐ D & A ☒ Ready to Prod.

18. Total Depth: MD 6715'  
TVD

19. Plug Back T.D.: MD 6641'  
TVD

20. Depth Bridge Plug Set: MD  
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)  
DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? ☒ No ☐ Yes (Submit analysis)  
Was DST run? ☒ No ☐ Yes (Submit report)  
Directional Survey? ☒ No ☐ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#		540'		286 CLASS G			
7-7/8"	5-1/2" J-55	15.5#		6685'		300 PRIMLITE		38'	
						425 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@ 6415'	TA @6287'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) GREEN RIVER			(CP3,2,1)see below	.49"	3	30
B) GREEN RIVER			(D2)(D1)see below	.36"	3	30
C) GREEN RIVER			(GB6)(GB4) see below	.36"	3	33
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
6272-6344'	Frac CP3,2 & 1 sds w/20,737#'s of 20/40 sand in 359 bbls of Lightning 17 fluid.
5378-5455'	Frac D2 & 1 sds w/ 85,716#'s of 20/40 sand in 677 bbls of Lightning 17 fluid.
4900-4946'	Frac GB4 & GB6 sds w/ 101,374#'s of 20/40 sand in 761 bbls of Lightning 17 fluid.

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
09/09/09	09/24/09	24	→	15	2	149			2-1/2" x 1-1/2" x 16' x 20' new Ctrl Hydrlic RHAC pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

\*(See instructions and spaces for additional data on page 2)

RECEIVED

OCT 14 2009

DIV. OF OIL, GAS & MINING

## 28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

## 28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

## 29. Disposition of Gas (Solid, used for fuel, vented, etc.)

USED FOR FUEL

## 30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 31. Formation (Log) Markers

## GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MRK GARDEN GULCH 1	4336' 4534'
				GARDEN GULCH 2 POINT 3	4664' 4954'
				X MRKR Y MRKR	5184' 5221'
				DOUGALS CREEK MRK BI CARBONATE MRK	5344' 5618'
				B LIMESTON MRK CASTLE PEAK	5759' 6227'
				BASAL CARBONATE TOTAL DEPTH (LOGGERS)	6628' 6719'

## 32. Additional remarks (include plugging procedure):

Perforate stage #1, CP3 sds @ 6342-44', CP2 sds @ 6320- 22', 6315- 17', CP1 sds @ 6272- 76' W/ 3 1/8" slick gun (19 gm charge, .49" EH, 21.92" pen, 120° phasing & 3 JSPF) for a total of 30 holes.  
 Perforate D2 sds @ 5458-60, 5453-55', D1 sds @ 5397-99' 5389-91' & 5378-80' w/ 3 1/8" port plug guns ( 11 gram, .36" HE, 120°, 16.82" pen,) w/ 3 spf for total of 30 shots.  
 Perforate GB6 sds @ 4941-46', GB4 sds @ 4908-12', 4900-4902' w/ 3 1/8" port plug guns (11 gram, .36" HE, 120°, 16.82" pen,) w/ 3 spf for total of 33 shots.

## 33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)     
 ☐ Geologic Report     
 ☐ DST Report     
 ☐ Directional Survey  
☐ Sundry Notice for plugging and cement verification     
 ☐ Core Analysis     
 ☐ Other:

## 34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)\*

Name (please print) Tammi LeeTitle Production ClerkSignature Date 10/08/2009

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> FEE
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 17th Street, Suite 2000 , Denver, CO, 80202		<b>8. WELL NAME and NUMBER:</b> LAMB 16-19-4-1
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0703 FSL 0637 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESE Section: 19 Township: 04.0S Range: 01.0W Meridian: U		<b>9. API NUMBER:</b> 43013342570000
<b>PHONE NUMBER:</b> 303 382-4443 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 3/11/2011	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input checked="" type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; display: inline-block; width: 100px; height: 15px;"></span>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
  
 The purpose of this procedure is to complete a latex cement squeeze of the D sand perforations which are a thief zone to offset injection wells. Production testing with RBP shows we shut off the water when we were above the D sands. However, we wish to open up both the CP's and the GB's (below D sand) at the same time which this job will allow.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 04/04/2011

By: *Dark K. Quist*

<b>NAME (PLEASE PRINT)</b> Jack Fulcher	<b>PHONE NUMBER</b> 303 383-4190	<b>TITLE</b> Engineer Tech
<b>SIGNATURE</b> N/A	<b>DATE</b> 3/22/2011	

## Lamb 16-19-4-1

Spud Date: 8/5/2009

Put on Production: 9/8/2009

GL: 5228' KB: 5240'

## Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 12 jts (527.14')

DEPTH LANDED: 538.99' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 286 sx class G cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 149 jts (6628.73')

DEPTH LANDED: 6685.44'

HOLE SIZE: 7-7/8"

CEMENT DATA: 300 sx Prem Lite and 425 sx 50/50 poz

CEMENT TOP AT: 38'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 172 jts (5482')

TUBING ANCHOR: 5494' KB

NO. OF JOINTS: 2 jts (32.4')

SEATING NIPPLE: 2-7/8" (1.1')

SN LANDED AT: 5529.2' KB

NO. OF JOINTS: 2 jts (63.2')

TOTAL STRING LENGTH: EOT @ 5596'

SUCKER RODS

POLISHED ROD: 1 1/2" x 30'

SUCKER RODS: 2 - 12' x 7/8" pony rods; 100 - 7/8" guided rods; 61 - 3/4" sucker rods; 53 3/4" guided rods; 6 - 1 1/2" weight bars

PUMP SIZE: 2 1/2" x 1 1/2" x 20" x 24'

STROKE LENGTH: 144"

PUMP SPEED, SPM: 5

FRAC JOB

9-9-09 6272-6344' Frac CP3,CP2, & CP1 sands as follows: Frac with 20,737# 20/40 sand in 170 bbls of Lightning 17 fluid.


9-9-09 5378-5460' Frac D2 & D1 sands as follows: Frac with 85,716# 20/40 sand in 513 bbls of Lightning 17 fluid.

9-9-09 4908-4946' Frac GB4 & GB6 sands as follows: Frac with 101,374# 20/40 sand in 606 bbls of Lightning 17 fluid.

11/24/2010 Pump change. Update rod and tubing details

PERFORATION RECORD

6342-6344'	3 JSPF	6 holes
6320-6322'	3 JSPF	6 holes
6315-6317'	3 JSPF	6 holes
6272-6276'	3 JSPF	12 holes
5458-5460'	3 JSPF	6 holes
5453-5455'	3 JSPF	6 holes
5397-5399'	3 JSPF	6 holes
5389-5391'	3 JSPF	6 holes
5378-5380'	3 JSPF	6 holes
4941-4946'	3 JSPF	15 holes
4900-4902'	3 JSPF	6 holes
4908-4912'	3 JSPF	12 holes

**Lamb 16-19-4-1**

703' FSL &amp; 637' FEL SE/SE

Section 19-T4S-R1W

Duchesne Co, Utah

API # 43-013-34257; Lease # FEE

CB 2/8/2011

**RECEIVED** Mar. 22, 2011

**NEWFIELD PRODUCTION COMPANY****Lamb 16-19-4-1 Cement Job****GMBU****Latex cement squeeze job on D Sands****AFE # 23774**

DOWNHOLE DATA							4 March 2011 Tom Walker
Elevation:	5228' GL; 5240' RKB						303-396-7843
TD:	6715'						
PBTD:	6641' current PBTD is RBP at 5716'						Fill levels unknown.
Surface casing:	8-5/8" 24# J55 @ 12' to 539' Cmt w/286 sx "G"						
Production casing:	5-1/2" 15.5# J55 @ 6685'. Cmt w/725 sx total						ID: 4.95"; Drift: 4.825" TOC @ 38'.
Tubing:	172 jts 2-7/8" 6.5# J55, TAC, 1 jt 2-7/8", SN, 2 jts 2-7/8"						TAC @ 5494' SN @ 5529' EOT @ 5529'
Rods/Pump	100 4 per 7/8", 61 3/4, 53 3/4" 4 per CDI 1-3/4 pump						
Existing Perfs:  							

**The purpose of this procedure is to complete a latex cement squeeze of the D sand perforations which are a thief zone to offset injection wells. Production testing with RBP show we shut off the water when we were above the D sands. However, we with to open up both the CP's and the GB's at the same time which this job will allow.**

**The well is standing full with water so this zone has high pressures (560 psi) at surface on the backside.**

**MI and spot 400 bbls fresh water tanks for cement job and cleaning well. Prior to filling tanks with water place 4 lbs of Frac-cide 1000 in each tank. Utilize this water for all treatments noted in the procedure below.**

**Minimize the use of pipe dope throughout this procedure. When necessary place dope on pin end only with paint brush.**

**This job must be performed safely. If for any reason it can't be performed safely, it should be shut down until it can be done safely.**



1. MIRU DDPU. Note this is a high pressure well. Recent well head pressures have been nearly 560 psi. Extreme caution should be taken when dealing with this well.
2. Flow back and as required kill well by bull heading kill weight brine into the backside of this well. Please contact Tom Walker with any questions or needed assistance on this step.
3. Seat pump and attempt to pressure test tubing to 3,000 psi.
4. POOH and visually inspect rods and pump. Complete tear down at pump shop.
5. Circulate kill weight brine as required to kill well as noted above.
6. ND wellhead and NU BOPE. Install stripping rubber or annular bag to allow for tubing and stinger to be pulled with 1000 psi pressure on pipe. Test as required.
7. Release TAC and TOO H and visually inspecting 2-7/8" tubing. Note we need good tubing for the upcoming cement job and drilling out. If tubing is suspect, please pick up a 2-7/8" N-80 work string. Report any schmoo or scale on tubing string (interval, depth, type) to Tom Walker. Lay down any joints with deposits.
8. PU bit and positive scraper and trip to assure well is cleaned out to RBP at 5716'. POOH
9. PU retrieving tool and pull RBP at 5716'.
10. MIRU eline unit. With eline set 5-1/2" 15.5# RBP at 5500' (in middle of casing joint below bottom D Sand perf at 5460'). POOH
11. With eline dump bail 20 feet (+/- 2.6 ft<sup>3</sup>) of sand on top of RBP (likely from 5500 to 5480'). POOH.
12. Dump bail on bag of calcium carbonate on top of sand.
13. Pull up hole with setting tool and allow cap to settle for 15 minutes. Tag cap and assure below perfs. POOH.
14. With eline set a cast iron cement retainer with check valve at 5355'. This is 19' below casing collar and 23' above top D Sand perf at 5378'. POOH
15. RDMO eline.
16. PU stinger for CICR and RIH. Tag top of CICR. Pick up 10'.
17. Hook up hard line to circulate down tubing and out annulus.
18. Load tubing and annulus with clean water. Note open GB sand perfs are above CICR which may take fluid.
19. Space out tubing so that we will have collar of full tubing joint at surface with knuckle joints and install stripping rubber or annular bag to allow for tubing and stinger to be pulled out of CICR with 1000 psi pressure on tubing.
20. Load hole and establish injection to surface again.

21. MIRU hot oil truck with ability to pump at good rates and pressure. They **MUST** to be able to record pressures and rates.
22. Sting into CICR and have hot oil truck establish stable injection rate into perfs with pressures below 1500 psi (estimated ISIP). Pump 50 bbls of water while monitoring injection rates. Assure no pressure increase on annulus.
23. **Relay information on injection test to Tom Walker and BJ for design of latex cement job. Have BJ complete leak off testing to determine cement qualities. Have them make a "hockey puck" of cement and keep that for Tom Walker.**
24. RDMO hot oil pumper when BJ is happy with testing results. Leave well as is over night waiting on BJ.
25. MIRU BJ Services cement pumper. Conduct pre job safety meeting and pressure test.

**Note that below may change depending on pre job leakoff test and fluid testing.**

26. Please see attached BJ program part of which is copied below. This may change depending injection test.

Note that we will pump 5 bbls of neat cement followed directly by 12 bbls of latex cement. This is due to the large perforated interval and wanting to get good coverage.

27. **If** well is tight with low injection rates, we will need to sting out of the CIDR and spot the cement to the end of the tubing and then string back in.
28. Attempt to get well to squeeze pressure. Hesitate if necessary for squeeze pressure. Max pressure to be 1500 psi.
29. Pull out of retainer with 1 bbl of cement remaining in tubing and dump that on retainer.
30. Pick up one joint and reverse circulate 2 tubing volumes if possible. Again, we have open perfs above us in GB sands.
31. POOH with tubing and lay down stinger.
32. WO cement to set up (overnight is best).
33. PU bit and drill out retainer and drill below perfs. Do not remove sand on top of RBP. Circulate bottoms up and POOH.
34. RIH with packer and set above squeeze perfs for pressure test.
35. Pressure test the squeeze holes to 500 psi.
36. If pressure test is good, swab well down for a negative test. Attempt to get tubing completely dry.
37. Monitor fluid inflow for at least one hour.
38. If negative test is good (less than 20' of inflow), POOH with packer.
39. If test is bad, rig up hot oil truck again to establish injection into squeeze perfs below packer to determine injection rate for potential resqueeze. Contact Tom Walker for procedure.

40. If good test, MU RBP retrieving tools and GIH to retrieve RBP. POOH with RBP.
41. PU and RIH with production tubing. ND BOPE, NU Tree and test as required.
42. PU and RIH with pump and rods as before.
43. PWOP. Monitor and carry well in test reports for one month.